Restoring Karehalli Amanikere and Doddasagarahalli Tanks, Devanhalli Taluk.

Items of work	Per	Quantity
Restoring Karehalli Amanikere Registered No. $\frac{122}{22}$ of Devanhalli Taluk.—		
Bund.—		
Earthwork raising bund to R. L. 56·00 including watering and tamping	C. yd.	6,587
Earthwork excavation	"	67
New stone work	"	836
Old stone work with new jelly	"	866
Turfing	S. yd.	6,853
Gravel backing to revetment	C. yd.	209
Clearing jungle with roots and picking old surface	Grade	29
New grade stones with bed slabs cutting figures painting complete	Each	30
Index stones new	"	30
Gauge stone with bed slab cutting figures painting complete	"	1
Date stone cutting figures painting complete	"	1
Registered number stone do	"	1
B. M. stones with bed slabs cutting figures painting complete	"	2
Waste weir.—		
Left waste weir.—		
Earthwork excavation	C. yd.	31
Burnt brick in surki mortar	C. ft.	446
Plastering with surki mortar nice	Sqr.	2·6
Plastering with surki mortar rough	"	1·83
Plastering with cement	"	0·81
Burnt stone slabs new	S. ft.	173
Old stone work with new jelly	C. yd.	79
New stone work	"	37
Right waste weir.—		
Earthwork excavation	C. yd.	110
Burnt brick in surki mortar	C. ft.	16·12
Plastering with surki mortar nice	Sqr.	2·52
Plastering with surki mortar rough	"	12·31
Burnt stone slabs new	S. ft.	167
Burnt stone slabs old	"	66
New stone work	C. yd.	1·0
Old stone work with new jelly	"	140
Jelly and rough stone filling below apron	"	46
Restoring Doddasagarahalli Tank Registered No. $\frac{100}{23}$ of Devanhalli Taluk.—		
Bund.—		
Earthwork raising bund to R. L. 56·09 including watering and tamping	C. yd.	13100
Earthwork excavation	"	523
Carting earth from weir cutting	"	209
New stone work	"	1953
Old stone work with old jelly	"	757
Turfing	S. yd.	104·74
Grave backing to revetment	C. yd.	75
Clearing jungle with roots and picking old surface	Grade	39
New grade stones with bed slabs cutting figures and painting, etc.	Each	40
Index stones new	"	40
Gauge stone with bed slab cutting figures and painting complete	"	1
Date stones cutting figures and painting, etc.	"	1
Registered number stone do	"	1
B. M. stones with bed slabs cutting figures and painting, etc., complete	"	2
Waste weir.—		
Earthwork excavation	C. yd.	359
Burnt brick in surki mortar	C. ft.	15·53
Plastering with surki mortar nice	Sqr.	2·00
Do do rough	"	6·50
Burnt stone slabs new	S. ft.	243
New stone work	C. yd.	203

C. VIJAYARANGAM NAIDU,
Executive Engineer.

KOLAR DIVISION.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, page 275, calling for tenders for restoring Vaichakurhalli tank, Registered No. 444 of Chintamani Taluk.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette* dated 23th March 1918 calling for tenders for restoring the Anehalli Mulagankere tank, R. No. 160 of the Mulbagal Taluk.

Dated 1st April 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 1st of May 1918, for constructing a Sericultural house at Kolar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M. on all days except Sundays and other holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Sericultural house at Kolar," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern circle who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for constructing a Sericultural house at Kolar.

No.	Items of work	Per	Quantity
1	Earthwork excavation and using the same to basement	C. yd.	88
2	Concrete in chunam	C. ft.	1,88
3	Burnt size stone in chunam	"	1,644
4	Burnt brick in chunam	"	3,621
5	Do Archwork	"	79
6	Burnt stone slabs dressed	S. ft.	289
7	Chunam plastering	Sqr.	61'44
8	Honney wood work wrought and put up	C. ft.	153'92
9	Teakwood ornamental eave board	R. ft.	302
10	Teakwood finials	Number	6
11	Teakwood doors panelled with frames iron hold fasts, hinges, bolts etc., complete.	S. ft.	184
12	Teakwood windows half glazed and half panelled, fixed outside with iron bars, hold fasts hinges, hooks etc., complete.	"	435
13	Teakwood circular ventilators	"	20
14	Roofing with 1st class Mangalore tiles on teak reepers 2"×1" with wood oiling and chunam border.	Sqr.	22'81
15	Ridge tiles set in mortar	R. ft.	128
16	Wood oiling 2 coats	Sqr.	15 06
17	Chocolate painting	"	20 29
18	Flooring with Mangalore tiles on 3" concrete bed and cement pointing ..	"	1'35
19	Teakwood double pillars with moulded bases and capitals, etc., complete ...	Number	8
20	Zinc sheets for valleys	S. ft.	210
21	Chunam pointing	Sqr.	3'35

V. V. KARVE,
Offg. Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

Attention of the public is invited to notification published in *Mysore Gazette*, dated 4th April 1918, pages 276-277 for restoring Adlapur Tank Registered No. 21 of Tumkur Taluk.

N. G. KRISHNA IYENGAR,
Offg. Executive Engineer.

MYSORE DIVISION.

Dated 30th March 1918.

"The public are hereby informed that repairs to the Girder Bridge in the 109th mile of the Mysore-Manantoddy road will be under repairs from the first week of April 1918 to about the end of May 1918 and will thus be closed for public traffic. A diversion road will be opened for public traffic."

Notice.

The attention of the public is invited to advertisement in detail published in the *Mysore Gazette*, dated 28th March 1918, calling for tenders for restoring Shirahalli tank, Registered No. 108, of Mandya Taluk.

P. SUBBA RAO,
For *Executive Engineer.*